NullahNet — presenter card · Theme 3 · 10 min (aim 9:15, keep 45 s spare)

Before you start: present `zonal-deck.pdf` from your own laptop. Open the dashboard in a second tab: `bash deliverables/serve_dashboard.sh`, then http://localhost:8765 (offline except map tiles). Backup slides 11–14: dashboard · how the twin works · limits · sources.

#	Time	Slide	Line to land
1	0:00–0:30	Title	"We make the city's existing booms accountable."
2	0:30–1:40	The leak	"The sea hands back what the drains gave it."
3	1:40–2:30	Our source	"We target the plastic nobody is paid to collect."
4	2:30–3:30	Who intercepts	"Two Interceptors cover two creeks. NullahNet is for the other booms."
5	3:30–4:40	Where it escapes	"Booms fail by being too square to the flow, not by filling up."
6	4:40–5:40	NullahNet	"No new civil works: when crews go, how booms sit, how contractors are paid."
7	5:40–6:50	Evidence 1	"Sensors alone don't help; sensors plus tide-aware timing do."
8	6:50–7:50	Evidence 2	"We report our weak numbers as plainly as our strong ones."
9	7:50–8:40	Conditions + cost	"A node costs under one percent of a boom."
10	8:40–9:15	Ask	"Give us three small outfalls in one ward."

Numbers to remember

- 5 million kg a year leaks from the metro region (survey estimate, The Ocean Cleanup 2026). Not a measurement.
- BMC booms: 9 today, 23 planned, ≈ ₹1 crore each. Upkeep: ₹14.5 crore for two years at six sites.
- Twin (SIMULATED): 92.5% of escaped plastic slips under or through the boom; overflow 5.9%.
- Tide-aware vs clear-when-full: −5.6%, better in 39 of 40 draws. Vs fixed schedule: −2.1%, small and uncertain.
- Fuse alone: −0.1%. It's for flood safety. One-way pocket (assumed): −5.0%.
- Sensor node: ₹83,481.98 of priced parts with enclosure, ≈ 0.8 % of a boom.

Fast answers

- *The Ocean Cleanup is here already?* Two creek mouths, 61 to 92 tonnes a year expected. We serve BMC's other booms.
- *Simulated?* Trust the ranking, not tonnes. Real rain, archived forecasts and fitted tide; 2024–25 held out; the circularity is stated.
- *Flooding?* The fuse opens at a set head; the pocket keeps its catch. We'll show the measured head-rise envelope.
- *Novel trap?* No. Floating tidal traps exist (Bandalong). Our contribution is the retrofit, the fuse, and the operations and evidence.
- *Camera at night?* Primary reading is range-sensor fill; the camera supports it.
- *Who pays?* BMC's existing boom budget; EPR is upside, because drain-plastic eligibility is not settled.

Don't say: "tamper-proof" · "blockchain" · "can't flood" · absolute tonnes from the twin · "our trap is new" · any guilt in the Mithi case · "we built the hardware" (it is PLANNED).